

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00740-00-00
Spot: SESESE Sec/Twnshp/Rge: 30-29S-8W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: SHEPARD C Well #: 1
County: KINGMAN Total Vertical Depth: 4215 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256		200 SX
PROD	4.5	4215	1290	125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/15/2010 11:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

9/10/10 SANDED BACK TO 3785' CAPPED WITH 4 SXS OF CEMENT - CUT CASING OFF AT 1290' PULLED CASING TO 1100' SPOTTED 35 SXS OF CEMENT WITH 100LBS OF HULLS - PULLED CASING TO 700' SPOTTED 35 SXS OF CEMENT AND 100 LBS OF HULLS - PULLED CASING TO 310' CIRCULATED TO SURFACE WITH 85 SXS OF CEMENT. 9-14-2010 TAGGED CEMENT AT 45' FROM SURFACE. 9-15-2010 TOPPED SURFACE OFF WITH 10 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4150	4170	CSG	
3836		CSG	

Remarks: QUALITY WELL SERVICE PROVIDED THE CEMENT - TICKET #5075

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)
RECEIVED

OCT 28 2010

KCC WICHITA

Form CP-2/3

✓