

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23845-00-00  
Spot: SESENW Sec/Twnshp/Rge: 27-24S-4E  
3004 feet from S Section Line, 3008 feet from E Section Line  
Lease Name: SOMMERS Well #: 1  
County: BUTLER Total Vertical Depth: 2640 feet

Operator License No.: 31389  
Op Name: NOBLE PETROLEUM, INC.  
Address: 3101 N ROCK RD STE 125  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	201		130 SX
T1	2.375	2505		
PKR	5.5	2505	1582	PACKER TYPE AND SETTING DEPTH: BAKER AD-1 SET @ 2505
PROD	5.5	2639		100 SX

Well Type: EOR UIC Docket No: E30553.1 Date/Time to Plug: 08/31/2010 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: GARY REED Company: NOBLE PETROLEUM INC. Phone: (316) 655-8775

Proposed Plugging Method: AS PER KCC RULES & REGS, 50 SXS ON BOTTOM, SHOOT CASING @ 1640', CEMENT 250'-0'

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/31/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2528', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 1582', LAYED CASING DOWN @ 274', CONSOLIDATED ESTABLISHED CIRCULATION AND PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. FINISHED LAYING DOWN CASING AND TOPPED WELL OFF TO SURFACE. PLUG DOWN 8-31-2010, 5:00 PM. CONSOLIDATED CEMENT TICKET #29113.

Perfs:

Top	Bot	Thru	Comments
2557	2612	CSG	

Remarks:

Plugged through: CSG

District: 02

Signed

*Duane Krueger*

RECEIVED (AN)

OCT 28 2010

KCC WICHITA