

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21286-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 5-21S-5W
3622 feet from S Section Line, 330 feet from W Section Line
Lease Name: ILENE PETERSON Well #: 6
County: MCPHERSON Total Vertical Depth: 3440 feet

Operator License No.: 31786
Op Name: OCFIW OIL COMPANY, INC.
Address: PO BOX 756
HARTINGTON, NE 68739

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	222		200 SX
PROD 7		3430	2020	135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2010 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVID BOLLENBACK WitnessType: PARTIAL
Date/Time Plugging Completed: 10/19/2010 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3315' AND CAP WITH 10 SX'S CEMENT. CUT CASING AT 2020' AND PULL TO 800' AND PUMP 50 SX'S COMMON CEMENT. PULL CASING TO 450' AND PUMP 50 SX'S COMMON CEMENT. PULL CASING TO 275' AND CIRCULATE 60-40 POZ, 4% GEL TO SURFACE. PULL CASING ON OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3365	3373	CSG	

RECEIVED
NOV 09 2010
KCC WICHITA

Remarks: COPELAND CEMENT TICKET #C-36640. ABOVE GPS READING INDICATES 3628' FSL, 5022' FEL.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)