

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20722-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 5-21S-5W
2110 feet from S Section Line, 5051 feet from E Section Line
Lease Name: LACKEY A Well #: 2
County: MCPHERSON Total Vertical Depth: 3413 feet

Operator License No.: 31786
Op Name: OFCIW OIL COMPANY, INC.
Address: PO BOX 756
HARTINGTON, NE 68739

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		175 SXS CMT
PROD	4.5	3402		230 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2010 4:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE INC Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: NONE
Date/Time Plugging Completed: 10/21/2010 6:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3300' AND CAP WITH 4 SX'S CEMENT. ATEMPT TO PULL CASING - CASING PARTED AT 10' SUB BELOW SURFACE. PERFORATE @ 800', 400', AND 265'. RUN TUBING TO 800' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 400' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 265' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3350	3360	CSG	

RECEIVED
NOV 04 2010
KCC WICHITA

Remarks: 60-40 POZ 4% GEL. COPELAND TICKET #C-36643. PIONEER PERF TICKET #31887.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)