

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20717-00-00  
Spot: NENESE Sec/Twnshp/Rge: 6-21S-5W  
2366 feet from S Section Line, 236 feet from E Section Line  
Lease Name: LACKEY B Well #: 1  
County: MCPHERSON Total Vertical Depth: 3410 feet

Operator License No.: 31786  
Op Name: OCFIW OIL COMPANY, INC.  
Address: PO BOX 756  
HARTINGTON, NE 68739

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		
PROD	4.5	3402	1706	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/26/2010 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: NONE  
Date/Time Plugging Completed: 10/26/2010 12:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3280' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF @ 1706' AND PULL TO 800' AND PUMP 35 SX'S CEMENT. PULL CASING TO 400' AND PUMP 35 SX'S CEMENT. PULL CASING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3367	3370	CSG	
3356	3358	CSG	
3332	3336	CSG	

RECEIVED  
NOV 04 2010  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND C-36648

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

VJK