

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21426-00-00
Spot: SWSE Sec/Twnshp/Rge: 15-33S-32W
705 feet from S Section Line, 1993 feet from E Section Line
Lease Name: FARM CREDIT BANK Well #: 1-15
County: SEWARD Total Vertical Depth: 3175 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	550		WITH 270 SX CMT
PROD	5.5	3178	0	WITH 175 SX CMT

Well Type: SWD UIC Docket No: D27074.0 Date/Time to Plug: 10/06/2010 11:30 AM
Plug Co. License No.: 34141 Plug Co. Name: MOHEGAN WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WATES Company: MOHEGAN WELL SERVICE, LLC Phone: (316) 681-0231

Proposed Plugging Method: PLUGGING. PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2010 6:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

RODS & TBG FISH @ 1704'. PERFORATE 5 1/2" @ 600'. RIH W/TBG TO 1600'.
PUMPED 250 SX CMT, CMT TO SURFACE INSIDE 5 1/2", NO CMT IN 5 1/2" X 8 5/8"
ANNULAR, RAN OUT OF CMT. (GOOD FLUID CIRCULATION IN 5 1/2" X 8 5/8"
ANNULAR) FLUSHED CMT OUT OF 5 1/2" & ANNULAR. BROUGHT OUT MORE
CMT. PUMPED 200 SX CMT. FILLED 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2940	3106		COUNCIL GROVE -
2544	2590		KRIDER

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

District: 01

RECEIVED
OCT - 8 2010
KCC DODGE CITY

Signed

Jack MacClaskey
(TECHNICIAN)

RECEIVED
OCT 14 2010
KCC WICHITA