

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10184-00-01
Spot: SESESW Sec/Twnshp/Rge: 14-33S-42W
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: KEPNER A Well #: 2
County: MORTON Total Vertical Depth: 3360 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	600		WITH 350 SX CMT
PROD	5.5	3353	831	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/10/2010 2:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLA & 25 SX CMT. PLUG AT 1650' WITH 25 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2010 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

OXY ATTEMPTED TO SQUEEZE CASING LEAKS @ 2050' DRILLED OUT CMT TO 1984' LOST CIRCULATION BECAUSE OF CASING LEAK AT +/- 1000'. LEFT CMT IN 5 1/2" CASING. 1ST PLUG AT 1980' WITH 25 SX CMT. 2ND PLUG AT 1650' WITH 25 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3252	3264		
3226	3246		
3206	3222		
3190	3202		
3102	3107		
3080	3096		
3068	3076		
3022	3026		
2996	3004		
2974	2984		
2960	2968		
2936	2952		
2872	2877		
2770	2778		
2740	2746		
2702	2710		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed

Jack MacLuskey
(TECHNICIAN)

RECEIVED

AUG 11 2010

KCC DODGE CITY

RECEIVED

AUG 19 2010

KCC WICHITA

Form CP 2/3