

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22308-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 31-31S-38W
2275 feet from S Section Line, 2170 feet from W Section Line
Lease Name: MLP CAVNER E Well #: 1
County: STEVENS Total Vertical Depth: 6145 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5950		WITH 2 SX CMT
SURF	8.625	1770		WITH 440 SX CMT
COND	20	45		
DVT		3004		
PROD	5.5	6145	372	WITH 565 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2010 2:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 5950' & 2 SX CMT. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2010 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 5950' & 2 SX CMT. LOAD HOLE WITH 115 BBLS MUD. 2ND PLUG RIHWT TO 1800' & PUMP 25 SX CMT. 3RD PLUG PULLED TBG TO 740' & PUMP 25 SX CMT. 4TH PLUG 4" STRETCH, CUT OFF 5 1/2" @ 372'. PUMP 25 SX CMT. 5TH PLUG PULL CASING TO 40' & PUMP 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6005	6017		ST LOUIS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

RECEIVED

JUL 13 2010

KCC DODGE CITY

Signed

(TECHNICIAN)

RECEIVED
JUL 23 2010
KCC WICHITA