

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20290-00-00
Spot: N2N2S2NW Sec/Twnshp/Rge: 32-30S-9W
1470 feet from N Section Line, 1320 feet from W Section Line
Lease Name: WESTERMAN Well #: 1
County: KINGMAN Total Vertical Depth: 4390 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		225 SX
PROD	4.5	4367		125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/16/2010 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

9-15-2010 SANDED BACK TO 4300' SPOTTED 4 SXS OF CEMENT. RAN TUBING IN TO 1500'-PERF CASING AND SPOTTED 50 SXS OF CEMENT - PULLED TUBING 1050' SPOTTED 35 SXS OF CEMENT - TAGGED AT 820' - PULLED TUBING TO 320' CIRCULATED 80 SXS. 9-16-2010 RAN TUBING BACK INTO 320' CIRCULATED TO SURFACE WITH 50 SXS OF CEMENT, 10 SXS DOWN BACKSIDE WITH 200 PSI. BACKSIDE HAD BEEN SQUEEZED @ 4367-4390 @ 2905-2935 @ 2802-2872 @ 760 @ 520'

Perfs:

Top	Bot	Thru	Comments
4367	4390	OH	MISSISSIPPI
2905	2935		
2802	2872		

Remarks: QUALITY WELL SERVICE TICKET #5079

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

RECEIVED

OCT 28 2010

10-28-10

KCC WICHITA

Form CP-2/3

✓