

#113.69

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25669-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 26-14S-16W  
4950 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SCHULTE Well #: 6  
County: ELLIS Total Vertical Depth: 3498 feet

Operator License No.: 6246  
Op Name: BENNETT & SCHULTE OIL CO., A GEN  
Address: 140 W WICHITA AVE  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	970	0	350 SX
PROD	5	3488	1494	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2010 9:00 AM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL CO. Phone: (785) 483-2721

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/12/2010 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:  
J&M Well Servicing sanded perfs from 3488' to 2820' and topped with 5 sxs cement.  
Log Tech shot pipe at 1494'.  
Pulled casing to 1450' - pumped 145 sxs cement with 300# hulls.  
Pulled casing to 1020' - pumped 40 sxs cement with 100# hulls mixed in.  
Pulled casing to 400' - pumped 100 sxs cement with 100# hulls to circulate cement to pit.  
Pulled casing and topped with 5 sxs cement - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3310	3312		LANSING
3204	3206		LANSING
3173	3175		LANSING
3106	3108		TORONTO
2862	2864		TOPEKA

12/07/10  
2011060295

RECEIVED  
OCT 18 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4590.

KCC WICHITA

Plugged through: CSG

District: 04

Signed [Signature]  
(TECHNICIAN) CM

Form CP-2/3

OCT 12 2010