

164.94

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20176-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 36-34S-16W
239 feet from S Section Line, 2222 feet from E Section Line
Lease Name: BALLET RANCH Well #: 5
County: COMANCHE Total Vertical Depth: 5075 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	888		WITH 450 SX CMT
PROD	4.5	5074	0	WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/30/2010 11:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: JASON BRUNS Company: BEREXCO LLC Phone: (316) 772-2971

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2010 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG RIHWT TO 5000' & PUMP 10 SX GEL, 200# HULLS, & 20 SX CMT. 2ND PLUG POOH TO 3100' & PUMP 10 SX GEL, 200# HULLS, & 20 SX CMT. 3RD PLUG CHECK TOC @ 2850'. PERFORATED CASING AT 900' & CIRCULATED CMT TO SURFACE WITH 300 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5020	5040		Miss Chert

12/07/10
2011060296

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Jerry W. Stapleton
PIR & II (TECHNICIAN)

RECEIVED
OCT 13 2010
KCC DODGE CITY

RECEIVED
OCT 15 2010
KCC WICHITA