

\$ 111.15

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20943-00-01
Spot: N2SWNW Sec/Twnshp/Rge: 30-18S-11W
3662 feet from S Section Line, 4597 feet from E Section Line
Lease Name: BAILEY UNIT Well #: T-1-W8 WIW
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212	0	175SX
PROD	5.5	3419	0	150 SX

Well Type: EOR UIC Docket No: E11512.2 Date/Time to Plug: 09/29/2010 8:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: ROBERT GRANT Company: BEREXCO LLC Phone: (785) 772-8160

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2010 12:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1050' - 675' - 200'.
Ran tubing to 3020' - tied to tubing and pumped 100 sxs cement with 250# hulls.
Pulled tubing to 2001' - pumped 100 sxs cement with 150# hulls.
Pulled tubing to 1020' - circulated cement to surface with 60 sxs cement and 100# hulls.
Pulled tubing - topped off with 5 sxs cement.
Max. P.S.I. 500#.
Surface pipe had been squeezed. Full of cement.

Perfs:

Top	Bot	Thru	Comments
3249	3251		
3192	3199		
3156	3158		
3115	3118		

12/07/10
201060297

RECEIVED
OCT 18 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #41953.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

Form CP-2/3

OCT 07 2010