

143.68

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24978-00-00  
Spot: N2N2SWNE Sec/Twnshp/Rge: 1-20S-21W  
1390 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: CODDINGTON Well #: 1  
County: NESS Total Vertical Depth: 4421 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221		WITH 160 SX CMT
PROD	5.5	4420	2787	WITH 175 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/01/2010 11:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 10/01/2010 6:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:  
1ST PLUG SAND TO 4420' & 2 SX CMT. 2ND PLUG AT 1976' WITH 40 SX CMT. 3RD PLUG AT 1212' WITH 80 SX CMT. 4TH PLUG AT 736' WITH 50 SX CMT. 5TH PLUG AT 260' WITH 40 SX CMT. 6TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4402	4419		MISSISSIPPIAN

12/8/10  
2011060786

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.  
Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
OCT - 7 2010  
KCC DODGE CITY

RECEIVED  
OCT 14 2010  
KCC WICHITA