

106.54

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02162-00-00
Spot: SESENW Sec/Twnshp/Rge: 18-19S-9W
2981 feet from S Section Line, 3407 feet from E Section Line
Lease Name: KATE Well #: 1
County: RICE Total Vertical Depth: 3278 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2870		
SURF	8.625	259		
PROD	5.5	3268		

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/27/2010 11:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES, SR. Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/27/2010 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 2870' AND CAP WITH 2 SX'S CEMENT. PERFORATE @ 1200', 850', AND 310'. RUN TUBING TO 1200' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 850' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 310' AND CIRCULATE CLASS A CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2921	2930	CSG	

12/09/10
201060280

Remarks: 60-40 POZ, 4% GEL. ALLIED CEMENT #30822. USED 200 SX'S TOTAL.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

OCT 06 2010

Form CP-2/3

KCC WICHITA

1/2K