

\$ 102.86

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21016-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 16-33S-6E
4987 feet from S Section Line, 2182 feet from E Section Line
Lease Name: FRY Well #: 5-A
County: COWLEY Total Vertical Depth: 3165 feet

Operator License No.: 32679
Op Name: AAS OIL CO., INC.
Address: 2508 EDGEMONT DR STE # 4
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	165	0	
PROD	4.5	3164	0	100 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/24/2010 10:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: LARRY STORM Company: CONSOLIDATED OIL WELL SERVI Phone: (316) 322-7022

Proposed Plugging Method: AS PER KCC RULES & REGS, WASHED HOLE @ 3060', PLUGGING ORDERS: 35 SXS @ 3060. 50 SXS @ STALNAKER. PERF @ 350'. CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 05/24/2010 7:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG@ 3049, CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. PULLED TBG @ 2030', CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. SHOT SQUEEZE HOLES @ 350'-351', RIH W/TBG @ 349', CONSOLIDATED MIXED & PUMPED 163 SXS CLASS A COMMON. CEMENT CIRCULATED. PLUG DOWN 5-24-2010, 7:00 P.M. CONSOLIDATED CEMENT TICKET #28285.

Perfs:

Top	Bot	Thru	Comments
3102	3108	CSG	

12/07/10
201060282

RECEIVED
NOV 02 2010
KCC WICHITA

Remarks:
Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

134