

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26030-00-00  
Spot: SENESE Sec/Twnshp/Rge: 6-15S-18W  
1636 feet from S Section Line, 383 feet from E Section Line  
Lease Name: DECHANT Well #: 1  
County: ELLIS Total Vertical Depth: 3682 feet

Operator License No.: 33353  
Op Name: WIESNER, TOM DBA TOM'S OIL  
Address: 3108 E 13TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2010 11:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: TOM ENGEL Company: WIESNER, TOM DBA TOM'S OIL Phone: (785) 628-1510

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE  
Date/Time Plugging Completed: 10/07/2010 12:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

1st. Plug at 3642' w/25 sxs.  
2nd. Plug at 1240' w/25 sxs.  
3rd. Plug at 525' w/100 sxs.  
4th. Plug at 270' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

RECEIVED  
OCT 18 2010  
KCC WICHITA