

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21085-00-01

Spot: SESENW

Sec/Twnshp/Rge: 24-14S-30W

2970 feet from S Section Line,

2970 feet from E Section Line

Lease Name: KINDERKNECHT A

Well #: 1

County: GOVE

Total Vertical Depth: 4450 feet

Operator License No.: 5420

Op Name: WHITE & ELLIS DRILLING, INC.

Address: PO BOX 48848

WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	293	0	160 sx 60/40 poz
PROD	4.5	4448	0	200 sx EA2

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/08/2010 9:30 AM

Plug Co. License No.: 31627

Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: DALLAS FLOWERS

Company: WHITE & ELLIS DRILLING, INC.

Phone: (785) 798-3641

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel.  
PC at 2131'. Bridge & plug at 4374'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/08/2010 1:45 PM

KCC Agent: PAT STAAB

**Actual Plugging Report:**

Whitetail Crude RIH to 4389'. Swift Cementing rigged to tubing and pumped 10 sxs gel - followed with 60 sxs 60/40 pozmix - 4% gel with 100# hulls mixed in.  
Pulled tubing to 2125'. Swift Cementing rigged to tubing and mixed and pumped 85 sxs cement with 200# hulls mixed in.  
Pulled tubing to 1060'. Swift Cementing rigged to tubing and pumped 85 sxs cement with 200# hulls mixed in.  
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 50 sxs cement.  
No shut in pressure.  
8 5/8" full on backside - visual check.

**Perfs:**

Top	Bot	Thru	Comments
4392	4395		
4312	4314		
4306	4307		
4072	4075		
3994	3996		
3902	3906		
3806	3832		

Remarks: SWIFT CEMENTING COMPANY-TICKET #18128.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED

SEP 13 2010

Form CP-2/3

SEP 09 2010

KCC WICHITA