

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00912-00-00
Spot: NESWNE Sec/Twnshp/Rge: 31-17S-1W
3742 feet from S Section Line, 1933 feet from E Section Line
Lease Name: ROBINSON Well #: 5
County: MCPHERSON Total Vertical Depth: 2666 feet

Operator License No.: 33978
Op Name: WHITE HAWK OIL COMPANY, LLP
Address: 15 E 5TH ST, STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	133		90 SX
PROD	5.5	2654		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2010 10:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: _____ Company: _____ Phone: (620) 654-8449

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2010 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

8/19/2010 SCOTT'S HAD DROPPED SAND A COUPLE OF DAYS AGO WHEN THEY LAID OUT WELL. WHEN I ARRIVED SCOTT'S HAD ALREADY TAGGED SAND @ 2600' AND CAPPED IT W/5 SXS CEMENT. THEY INTEND TO SALVAGE AS MUCH 5 1/2" CASING AS THEY CAN THEN WILL BAIL DOWN HOLE AND PLUG WITH SLURRY MIX. I WAITED TILL THEY TRIED TO PULL STRETCH TO SEE HOW MUCH CASING WAS FREE, VERY LITTLE SEARCH. THEY THEN DECIDED TO RIP CASING AT 250' TO 300' AND DO TOP PLUG. SCOTT'S TRIED RIPPING CASING FOR AN HOUR AT 300' NO FREE POINT. THEN WAS DECIDED TO RUN 1" DOWN THE BACKSIDE AND CIRCULATE CEMENT. THEN RUN 1" DOW INSIDE OF 5 1/2" AND CIRCULATE TO SURFACE. SCOTT'S WENT TO GET 1" DURING LUNCH AND CONSOLIDATED TO BE HERE @ 1:30 PM. AFTER LUNCH SCOTT'S RAN 1" DOWN TO 190' ON THE BACKSIDE AND TAGGED SOLID. CONSOLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE PUMPING 105 SXS. SCOTT'S THEN PULLED 1" AND RAN IT DOWN THE 5 1/2" TO 260'. CONSOLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE PUMPING 42 SXS. SCOTT'S PULLED TUBING AND WASHED UP FINISHED AT 3:45 PM. THEY USED 147 SXS 60/40 POS W/4% GEL TK #28576. 8/23/2010 CHECKED TOP PLUG AND FOUND BACKSIDE TO BE DOWN ABOUT 10' AND PLUG INSIDE 5 1/2" DOWN 140'. I TALKED TO BRUCE DIRKS W/WHITE HAWK. BRUCE ASKED TO USE SLURRY TO TOP OFF WELL. I AGREED AND BRUCE HAD THEM SET UP FOR 2:00 PM WITH 2YDS.

Perfs:

Top	Bot	Thru	Comments
2654	2666	OH	

Remarks: WELL DOWN MORE THAN 10 YEARS

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
SEP 01 2010
KCC WICHITA