

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23009-00-00  
Spot: NESENE Sec/Twnshp/Rge: 31-23S-13W  
3550 feet from S Section Line, 410 feet from E Section Line  
Lease Name: CORNWELL Well #: B  
County: STAFFORD Total Vertical Depth: 4144 feet

Operator License No.: 5044  
Op Name: WHITE PINE PETROLEUM CORPORATI  
Address: 110 S MAIN ST STE 500  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3810		
SURF	8.625	388		WITH 250 SX CMT
PROD	5.5	4142	2030	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2010 3:45 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3617' & 5 SX CMT. PLUG AT 810' WITH 10 SX GEL & 50 SX CMT. PLUG AT 410' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/26/2010 3:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3525' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 814' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 412' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED  
AUG 27 2010  
KCC DODGE CITY

Signed

*Richard W. Lacey*

(TECHNICIAN) RECEIVED

SEP 01 2010  
KCC WICHITA