

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21458-00-00
Spot: SWNENE Sec/Twnshp/Rge: 32-16S-29W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: DICKEY Well #: 1
County: LANE Total Vertical Depth: 4580 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	311		WITH 185 SX CMT
PROD	4.5	4469	0	WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2010 12:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 4100' & 4 SX CMT. PLUG AT 2250' WITH 10 SX GEL & 50 SX CMT. CIRCULATE CMT FROM 1200' TO SURFACE WITH 50 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 06/28/2010 3:15 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

CEMENTED FROM 2000' TO 0'. SAND BACK TO 4400' & 4 SX CMT. 1ST PLUG AT 2250' WITH 10 SX GEL & 25 SX CMT. 2ND PLUG 1200' WITH 75 SX CMT. CMT CIRCULATED TO SURFACE. TOOH W/TBG & TOP OFF WITH 5 SX CMT. 4 1/2" X 8 5/8" ANNULUS WAS FULL. COULD NOT PUMP IN.

Perfs:

Top	Bot	Thru	Comments
4421	4444		
4295	4299		
4169	4173		
4144	4148		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
JUN 30 2010
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 06 2010
CONSERVATION DIVISION
WICHITA, KS