

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20410-00-00
Spot: NWNENW Sec/Twnshp/Rge: 9-19S-20W
5003 feet from S Section Line, 3456 feet from E Section Line
Lease Name: FRICK A Well #: D1
County: RUSH Total Vertical Depth: 4370 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1183		
SURF	8.625	382		WITH 175 SX CMT
PROD	5.5	1214	0	WITH 400 SX CMT

Well Type: SWD UIC Docket No: D16317.0 Date/Time to Plug: 07/01/2010 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY D. BRINEY, FOREM Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: RIH W/TBG & FILL WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2010 2:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

WORKED TBG TO 850'. HOLE FULL OF CEDAR HILLS SAND TO THAT POINT. PUMPED 130 SX CMT DOWN TBG WITH 50# HULLS AFTER 17 BBLs OF SLURRY. CIRCULATED CMT TO SURFACE UP 5 1/2". PULLED TBG & TOPPED OFF 5 1/2" WITH 25 SX CMT. CASING WAS ON A CASING HANGER. CUT A HOLE IN IT & RAN A 10' ROD DOWN 8 5/8". SURFACE PIPE FULL OF WATER. 7/22/10: OPERATOR ORANGEPEELED SURFACE PIPE TO THE 5 1/2" CASING. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 400# WITH 1/2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
880	1080		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
AUG - 3 2010
KCC DODGE CITY

RECEIVED
AUG 10 2010
KCC WICHITA

Form CI 27