

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20611-00-01
Spot: NWNESESW Sec/Twnshp/Rge: 19-15S-29W
1277 feet from S Section Line, 3211 feet from E Section Line
Lease Name: YORK Well #: 2 SWD
County: GOVE Total Vertical Depth: 4184 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	308	0	185
PROD	4.5	2018	0	500 sxs

Well Type: SWD UIC Docket No: D21430.0 Date/Time to Plug: 09/14/2010 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2010 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 308' w/185 sxs cement.
4 1/2" production casing set at 2018' w/500 sxs cement.
Ran tubing to 1597' - contacted stuck packer - pumped 125 sxs cement mixed with 275# hulls - cement to surface - pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 50 sxs cement - cement at surface.
Connected to 8 5/8" surface casing - pumped 1/2 sack cement - casing head ruptured.

Perfs:

Top	Bot	Thru	Comments
1742	1762		
1598	1742		

Remarks: SWIFT SERVICES CEMENTING COMPANY-TICKET #18,133.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

RECEIVED

SEP 20 2010

Form CP-2/3

KCC WICHITA

SEP 15 2010