

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22601-00-00
Spot: NENESW Sec/Twnshp/Rge: 15-24S-14W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SUITER Well #: 1
County: STAFFORD Total Vertical Depth: 4100 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	290		WITH 300 SX CMT
PROD	4.5	4098	2032	WITH 110 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2010 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL Phone: (316) 682-1537

Proposed Plugging Method: SAND TO 4000' WITH 4 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: NONE
Date/Time Plugging Completed: 11/03/2010 11:15 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4000' & TOP WITH 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 908' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 312' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4060	4064		MISS CHERT
4056	4060		MISS CHERT

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

RECEIVED
NOV - 9 2010
KCC DODGE CITY

Signed Jerry W Stapleton
(TECHNICIAN)
PIRT II

[Signature]
Form 11/2/3