

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20153-00-00
Spot: SENESW Sec/Twnshp/Rge: 34-19S-12W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: MUSENBERG Well #: 2
County: BARTON Total Vertical Depth: 3422 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	200 SX
PROD	4.5	3421	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2010 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: K&N PETROLEUM, INC. Phone: (620) 793-6005

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 6 sxs gel.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/13/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs: 1550' - 625' - 200'.
Ran tubing to 3200' - pumped 6 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1520' - pumped 75 sxs cement with 100# hulls.
Pulled tubing to 1250' - circulated cement to surface with 60 sxs cement.
Pulled tubing - tied to casing and pumped 70 sxs cement - circulated cement out surface.
Shut in.

Perfs:

Top	Bot	Thru	Comments
3362	3372		

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35108.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED

SEP 20 2010

Form CP-2/3

KCC WICHITA

SEP 15 2010