

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20275-00-00  
Spot: S2NWSE Sec/Twnshp/Rge: 34-19S-12W  
1650 feet from S Section Line, 2210 feet from E Section Line  
Lease Name: MUSENBERG Well #: 3  
County: BARTON Total Vertical Depth: 3415 feet

Operator License No.: 3208  
Op Name: K & N PETROLEUM, INC.  
Address: 1105 WALNUT  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	214	0	200 sx cement
PROD	4.5	3413	0	150 sx cement

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/10/2010 12:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ED NEMNICH Company: K&N PETROLEUM, INC. Phone: (620) 793-6005

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Old well - junk left in the well at 1400' in 1993.  
Entered well 08/09/2010 - drilled and milled on junk in the well - could not get past junk - decided to plug well.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/10/2010 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 1385' - tied to tubing and pumped 100 sxs cement.  
Pulled 660' - circulated cement to surface with 75 sxs cement.  
Pulled tubing.  
Tied to backside and pressured up to 300# P.S.I. - would not take cement.  
Tied to casing and pumped 15 sxs cement.  
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3370	3374		
3367	3369		
3351	3356		

Remarks: COPELAND ACID AND CEMENTING-TICKET #34557.

Plugged through: CSG

RECEIVED

AUG 18 2010

KCC WICHITA

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

Form CP-2/3

AUG 16 2010

LONITA, INC. #3 MUSENBERG 34-19-12W  
 WICHITA, KS. C S2 NW SE  
 Contr. LEBEN DRIG. Cty. BARTON  
 Geol. R. F. HARTMAN Pool FT. ZARAH  
 E. 1806 KB Cm. 9/14/68 Cp. 11/7/68 IPPMP 25 BOPD +33%  
 W/ARB 3367-74  
 API 15-009-20,275


LOG Tops	Depth	Datum	Csg. 8" 214/200 SX; 4 1/2" 3413/150 SX; DST 3100-3115/1', 15'M, BHP 39-31#/30", FP 23-23#
TOP	2703	- 897	
HEEB	2968	-1162	DST 3119-3136/1', 420' GIP, 240' 80 SP GGSW, BHP 693-606#, FP 54-98#
BR LM	3088	-1282	
LKC	3102	-1296	DST 3140-3166/1', 15'M, BHP 967-520#/30" FP 31-48#
BKC	3344	-1538	
CONG	3350	-1544	DST 3221-3244/37", 20'M, BHP 54-40#, FP 15-23#
ARB	3354	-1548	
LTD	3414	-1608	DST 3352-3360/42", 50'M, 5' HOCM, BHP 734-676#/30", FP 11-18#
RTD	3415	-1609	DST 3361-3374/30", 40'M, 5' FREE OIL, BHP 746-711#/30", FP 30-35#
			DST 3365-3384/1', 420' SMO, 295' FREE OIL, BHP 676-560#, FP 95-262#
			PF 23/3367-74 1/2, A 1500, SWB 42 BF & 33% WTR

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS