

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20126-00-00
Spot: E2E2SW Sec/Twnshp/Rge: 34-20S-38W
1310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: CALDWELL C Well #: 5
County: WICHITA Total Vertical Depth: 4950 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4149		WITH 2 SX CMT
SURF	8.625	319		WITH 155 SX CMT
DVT		1784		TOC @ 1560
PROD	5.5	4950	0	WITH 280 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2010 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BILL LOWE Company: KAISER-FRANCIS OIL COMPANY Phone: (405) 262-5511

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2010 12:15 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOF @ 4176'. CIBP @ 4149' WITH 2 SX CMT. PERFORATE AT 1070'. ESTABLISH RATE. PUMP 85 SX CMT, 100# HULLS, THEN 95 SX CMT. SHUT IN PRESSURE 400#. PUMP 150 SX CMT DOWN ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
4770	4786		OA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JUL 22 2010
KCC DODGE CITY

Signed

[Signature]

(TECHNICIAN)

RECEIVED
AUG 04 2010
8-4-10
KCC WICHITA

Form CP-20