

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20897-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 5-15S-34W
1825 feet from S Section Line, 640 feet from E Section Line
Lease Name: SOWERS Well #: 1
County: LOGAN Total Vertical Depth: 5227 feet

Operator License No.: 34162
Op Name: NEW GULF OPERATING LLC
Address: 6310 E. 102ND ST.
TULSA, OK 74137

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/28/2010 5:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DANNY Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: NONE
Date/Time Plugging Completed: 10/28/2010 6:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st. Plug at 4977' w/25 sxs.
2nd. Plug at 2340' w/25 sxs.
3rd. Plug at 1180' w/100 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

RECEIVED

NOV 15 2010

Form CP-2/3

OCT 29 2010

KCC WICHITA