

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20751-00-00  
Spot: S2NWSWNW Sec/Twnshp/Rge: 27-11S-33W  
1775 feet from N Section Line, 330 feet from W Section Line  
Lease Name: GELWICKS TRUST Well #: 1  
County: LOGAN Total Vertical Depth: 4695 feet

Operator License No.: 32210  
Op Name: SPRING, HARRY A.  
Address: 911 W BROADWAY BOX 1788  
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	266	0	225 SX CMT
T1	2.875	3005		
PROD	5.5	4684	0	200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2010 10:30 AM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: MIKE DAVIGNON Company: SPRING, HARRY A. Phone: (785) 216-0062

Proposed Plugging Method: Ordered 405 sxs 60/40 pozmix - 4% gel - 200# hulls - 11 sxs gel.  
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2010 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 266' w/225 sxs cement.  
5 1/2" production casing set at 4684' w/200 sxs cement.  
TD 4695'. PBTD 4664'.  
Connected to 5 1/2" production casing - pumped 75 sxs cement mixed with 200# hulls - followed with 11 sxs gel and 300 sxs cement.  
Max. P.S.I. 1000#. S.I.P. 1000#.  
8 5/8" surface casing was full of cement.  
Plug complete.

Perfs:

Top	Bot	Thru	Comments
4613	4625		
4302	4308		
4252	4262		
4218	4224		

Remarks: ALLIED CEMENTING COMPANY-TICKET #35,674.

Plugged through: CSG

District: 04

Signed Darrel Dipman (TECHNICIAN) CM

RECEIVED

NOV 17 2010

Form CP-2/3

NOV 12 2010

KCC WICHITA