

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19229-00-00
Spot: SENESE Sec/Twnshp/Rge: 32-15S-11W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: DAVIDSON Well #: 2
County: RUSSELL Total Vertical Depth: 3274 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	286	0	175 SX
PROD	5.5	3268	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2010 3:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: ROBINOWITZ OIL COMPANY Phone: (620) 786-4258

Proposed Plugging Method: Ordered 300 sxs 60/40 ozmix - 4% gel - 500# hulls - 12 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2010 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1400' - 700' - 450' - 150'.
Ran tubing to 3224' - pumped 12 sxs gel - followed with 50 sxs cement with 200# hulls.
Pulled tubing to 1400' - pumped 130 sxs cement with 200# hulls.
Pulled tubing to 700' - circulated to surface with 25 sxs cement and 100# hulls.
Pulled tubing - tied to casing and pumped 90 sxs cement - circulated out surface pipe. Shut in.

Perfs:

Top	Bot	Thru	Comments
3268	3274		ARBUCKLE OH

Remarks: LEASE ALSO KNOWN AS DAVIDSON #1B. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

CM

AUG 30 2010 Form CP-2/3

KCC WICHITA

AUG 27 2010