

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19242-00-01
Spot: NESESE Sec/Twnshp/Rge: 32-15S-11W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: DAVIDSON Well #: 4
County: RUSSELL Total Vertical Depth: 3284 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	289	0	175 SX
PROD	5.5	3269	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2010 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY A GE Phone: (918) 481-7130

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel spacer.
Lease workup by Pat Staab.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2010 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed at 1400' - 700' - 450' - 150'.
D.S&W Well Service RIH with tubing to 3224'.
Copeland Cementing rigged to tubing and pumped 12 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1550' - rigged to tubing and mixed and pumped 160 sxs cement with 300# hulls to circulate cement to pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 350#.
Rigged to 8 5/8" - pumped 5 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3269	3284		Arbuckle-open hole

RECEIVED
AUG 31 2010

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #34594.

KCC WICHITA

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

Form CP-2/3

AUG 27 2010

ROBINOWITZ OIL

#4 DAVIDSON

32-15-11W
NE SE SE

Contr. SHOLOM DRILLING

RUSSELL County

E. 1819KB Comm. 3/20/63 Comp. 5/9/63 IP. PMP 100 BOPD, NW/
ARB 3269-73

SMP Tops	Depth	Datum
TOP	2611	-792
HEEB	2853	-1034
TOR	2873	-1054
DOUG	2885	-1066
LANS	2944	-1125
ARB	3264	-1445
TD	3283	-1464

Casing

8" 288/175 sx:

5" 3269/100 sx:

DST 3186-3273/60", 70' OCM, BHP
900#/20"-630#/30", FP 10-100#:

DD 3283: FU 2600' - OIL/12 HRS,
NATL: POP:

DAVIDSON

+	+	+
+	+	+
+	+	+

GEOL-BOB PRICE

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS