

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07292-00-00
Spot: E2SENV Sec/Twnshp/Rge: 20-15S-13W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ETHYL SYLVA Well #: 1
County: RUSSELL Total Vertical Depth: 3171 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY, A GENE
Address: 4200 E SKELLY DR STE 620
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3127		
SURF	8.625	411	0	275 SX
PROD	5.5	3127	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2010 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 587-3936

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 850' - 450' - 225'.
Ran tubing to 3069' - pumped 11 sxs gel - followed with 50 sxs cement with 100# hulls.
Pulled tubing to 1500' - pumped 70 sxs cement with 150# hulls.
Pulled tubing to 850' - circulated to surface with 50 sxs cement with 100# hulls.
Pulled tubing to 450' - circulated cement to surface with 65 sxs cement with 150# hulls.
Pulled tubing. Tied to surface pipe. Pressured up - would not take fluid.
Max. P.S.I. 400#.
Topped off casing with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3089	3094		LKC

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKE #35987.

Plugged through: CSG

RECEIVED
SEP 03 2010
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

SEP 01 2010