

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-07318-00-00  
Spot: NWSWN Sec/Twnshp/Rge: 20-15S-13W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: ETHYL SYLVA Well #: 3  
County: RUSSELL Total Vertical Depth: 3246 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY, A GENE  
Address: 4200 E SKELLY DR STE 620  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3180		
CIBP		3234		
SURF	10.75	237	0	175 SX
PROD	5.5	3234	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/30/2010 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DON DEGENHARDT Company: ROBINOWITZ OIL COMPANY Phone: (620) 587-3936

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 8 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/30/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 800' - 450' - 225'.  
Ran tubing to 2879' - pumped 8 sxs gel - followed with 60 sxs cement with 200# hulls.  
Pulled tubing to 1500' - pumped 70 sxs cement with 100# hulls.  
Pulled tubing to 800' - circulated to surface with 40 sxs cement with 100# hulls.  
Pulled tubing to 450' - circulated cement to surface with 60 sxs cement.  
Pulled tubing.  
Tied to surface pipe - pumped 15 sxs cement - pushed cement out of casing - shut in.

Perfs:

Top	Bot	Thru	Comments
3230	3234		ARBUCKLE
3194	3204		CONGLOMERATE
3001	3005		LKC

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

RECEIVED

SEP 03 2010

KCC WICHITA

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

SEP 01 2010