

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03163-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 20-10S-23W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DIEBOLT LKC UNIT Well #: 4-4  
County: GRAHAM Total Vertical Depth: 3890 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	220	0	140 SX
PROD 7		3389	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2010 12:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 575 sxs 60/40 pozmix - 4% gel - 600# hulls - 20 sxs gel spacer.  
Perforated at 1950' - 1070' - 270'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2010 9:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3778' - pumped 20 sxs gel spacer - followed with 100 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1954' - pumped 190 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 1018' - pumped 75 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 494' - pumped 100 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled all tubing. Let well set over night.  
Topped off 7" casing with 25 sxs 60/40/ pozmix - 4% gel.  
Hooked to 10 3/4"x 7" annulus. Pumped 45 sxs 60/40 pozmix - 4% gel.  
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3845	3851		LKC 'J'
3828	3835		LKC 'I'
3743	3746		LKC 'F'
3600	3604		PLATTSMOUTH

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4060.

Plugged through: TBG

RECEIVED  
SEP 03 2010

KCC WICHITA

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

AUG 30 2010

MID CONTINENT

#4 G BROWN

20-10-23W  
NW NE NE

Contr. GABBERT-JONES GRAHAM County

E 2386RB Comm. 7-3-54 Comp. 8-13-54 IP 3000 BOPD  
BOMB POT


Tops	Depth	Datum
LANS	3654	-1268
TD	3890	-1504

Casing

10" 220  
7" 3389

DST 3816-31/10 $\frac{1}{2}$  HRS, 2750'  
OIL, BHP 1090#  
PERF 3828-35: ACID 2000:

HAPPY SE POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS