

F 61.88

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20523-00-00  
Spot: W2SW Sec/Twnshp/Rge: 12-18S-16W  
1379 feet from S Section Line, 597 feet from W Section Line  
Lease Name: MAULER Well #: 1-12  
County: RUSH Total Vertical Depth: 1904 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	450		WITH 225 SX CMT
L1		1830		CMT CIRCULATED
PROD	4.5	1903	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/25/2010 10:30 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: NATHAN WOODS Company: COPELAND ACID & CEMENT, INC. Phone: (316) 524-1225

Proposed Plugging Method: FILL ALL STRINGS WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/25/2010 11:35 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

VISUALLY CHECKED 8 5/8" X 4 1/2" ANNULUS FULL OF CMT. PRESSURED 4 1/2" X 3" ANNULUS TO 500 PSIG WITH 1 SX CMT. PUMPED DOWN 3" WITH 200# HULLS & 105 SX CMT. MAXIMUM PRESSURE 1200 PSIG. SHUT IN PRESSURE 1000 PSIG.

Perfs:

Inv. dt: 12/15/10  
Inv. #: 2011060294

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
NOV - 1 2010  
KCC DODGE CITY

RECEIVED  
NOV 10 2010  
KCC WICHITA

Form C-10