

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20191-00-00
Spot: NESWSW Sec/Twnshp/Rge: 16-14S-10W
909 feet from S Section Line, 4298 feet from E Section Line
Lease Name: SOUKUP A Well #: 3
County: ELLSWORTH Total Vertical Depth: 2930 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2400		
SURF	8.625	250		150 SXS CMT
PROD	4.5	2925		250 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2010 11:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: NO PERFS LISTED ON CP-1. THAT INFO OBTAINED FROM KEN BUEHLER. MIRU, CK BOTTOM. SET CIBP @ 2400' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1200', 850', AND 300'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 850' AND PUMP 35 SX'S, PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 08/02/2010 2:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 2400' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1200, 850' AND 300'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON 4.5" CASING AND CIRCULATE CEMENT UP SURFACE CASING. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2832	2852	CSG	
2452	2458	CSG	

Remarks: 60-40 POZ, 4% GEL. PERF TECH #7395. QUALITY WELL TICKET #4129.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
AUG 17 2010
KCC WICHITA