

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20527-00-00
Spot: NENESE Sec/Twnshp/Rge: 23-14S-11W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: PRINC Well #: 5
County: RUSSELL Total Vertical Depth: 2257 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209	0	160 SX
PROD	5.5	2256	0	80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2010 9:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 200' - 560' - 1400'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2010 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2201' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1143' - pumped 100 sxs cement with 100# hulls. - cement circulated.
POOH. Hooked onto casing and pumped 35 sxs cement - cement circulated out the Braden head.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4541.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

RECEIVED
OCT 04 2010

Form CP-2/3

SEP 30 2010

KCC WICHITA