

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20530-00-00
Spot: NWNESE Sec/Twnshp/Rge: 23-14S-11W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: PRINC Well #: 6
County: RUSSELL Total Vertical Depth: 2150 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212	0	160 SX
PROD	5.5	2149	0	50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2010 9:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (787) 483-1821

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 1200' - 500' - 214'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2010 1:15 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing 1997' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 1141' - pumped 100 sxs cement with 100# hulls - cement circulated.
POOH. Hooked to casing and pumped 35 sxs cement - circulated out of Braden head.

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET 34543.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED
OCT 07 2010
KCC WICHITA

Form CP-2/3

OCT 05 2010