

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20751-00-00
Spot: E2W2NW Sec/Twnshp/Rge: 21-24S-13W
3960 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BECKERDITE Well #: 1
County: STAFFORD Total Vertical Depth: 3410 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1800		WITH 2 SX CMT
SURF	8.625	280		WITH 200 SX CMT
PROD	4.5	2034	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/28/2010 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: SET CIBP @ 1800' & 2 SX CMT. PERFORATE AT 800'. CIRCULATE CMT TO SURFACE UP 8 5/8" X 4 1/2".

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2010 3:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 1800' WITH 2 SX CMT ON TOP WITH DUMP BAILER. PERFORATED AT 800'. PUMPED 285 SX CMT DOWN 4 1/2" & LOST CIRCULATION UP 8 5/8" AFTER 230 SX CMT. SDON. 7/29/10: PUMPED 100 SX CMT DOWN 8 5/8" X 4 1/2" ANNLULUS @ 400#. TOPPED OFF 4 1/2" WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1868	1869		
1853	1858		

12/03/10
2011060242

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED
AUG - 3 2010
KCC DODGE CITY

RECEIVED
AUG 10 2010
KCC WICHITA