

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21354-00-00
Spot: NESWNW Sec/Twnshp/Rge: 24-20S-16W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: OETKIN Well #: 4
County: PAWNEE Total Vertical Depth: 4065 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3780		WITH 2 SX CMT
SURF	8.625	1084		WITH 400 SX CMT
PROD	5.5	3888	1658	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING, INC. Phone: (785) 625-6374

Proposed Plugging Method: CIBP @ 3780' WITH 2 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2010 11:05 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 3780' & 2 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1115' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 382' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3812	3827		ARBUCKLE

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

JUN 25 2010

KCC DODGE CITY

RECEIVED

JUL 14 2010

KCC WICHITA

Form 27-3/3