

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24455-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 30-20S-15W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: UNRUH Well #: 2
County: BARTON Total Vertical Depth: 3865 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|------------|
| SURF | 8.625 | 1062 | 0 | 400 SX CMT |
| PROD | 5.5 | 3864 | 1739 | 75 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (620) 793-5838

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Shot casing off at 1739' - pumped 150 sxs cement with 200# hulls.
Pulled casing to 1750' - pumped 40 sxs cement with 100# hulls.
Pulled to 500' - pumped 105 sxs cement with 200# hulls.
Pulled casing and topped off with 5 sxs cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3804 | 3807 | | |
| 3797 | 3800 | | |
| 3790 | 3792 | | |
| 3784 | 3786 | | |

Remarks: ALLIED CEMENTING COMPANY-TICKET #36777.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

RECEIVED

JUL 29 2010

Form CP-2/3

JUL 26 2010

KCC WICHITA

STATE: KANSAS COUNTY: BARTON 30-20S-15W
FIELD: PAWNEE ROCK 3/4 MI NW ASH CREEK FLD (ARBUCKLE) SW NW NW
OPER: IANNITTI OIL 4290 FSL 4950 FEL SEC
WELL: 2 UNRUH WELL CLASS: WOE ELEV: 2050 GR
API: 15-009-24455 STATUS: OIL
SPUD: 12/27/90 COMP: 07/01/91
DTD: 3900 LTD: FTD: ARBUCKLE PBD:

LOC: 3 MI NW PAWNEE ROCK, KS

IP: COMP 7/1/91, IPP 60 BOPD, 15 BWPD PROD ZONE- ARBUCKLE 3784-3800 GROSS
NO CORES OR DSTS (ARBUCKLE EXTENSION)

LOG TOPS:
ARBUCKLE 3780 -1730 |
TD 3900 -1850 |

LOG TYPES NOT RPTD

CSGS: RAN SURF & PROD CSG: DRLG COMP 01/06/91 RIG REL 01/07/91
PRODUCING INTERVAL: PERF (ARBUCKLE) 3784-3800 GROSS, TREATMENT NOT RPTD

OPER ADD: BOX 308, GREAT BEND, KS, 67530 PHONE (316) 792-1922;
CONTR: WOODMAN & IANNITTI RIG # 1

COPYRIGHT 1991 PETROLEUM INFORMATION CORPORATION

DATE 11/27/91 CARD #00037-KS