

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24485-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 30-20S-15W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: UNRUH Well #: 3
County: BARTON Total Vertical Depth: 3870 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1065	0	400 SX
PROD	5.5	3869	1754	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2010 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (865) 675-1554

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 1754' - pulled up to 1750' - pumped 150 sxs cement with 300# hulls.
Pulled casing to 975' - pumped 40 sxs cement.
Pulled casing to 500' - pumped 105 sxs cement - circulated to surface.
Pulled casing and topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3808	3811		
3798	3801		
3785	3788		

Remarks: ALLIED CEMENTING COMPANY-TICKET #36780.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

RECEIVED
JUL 29 2010

Form CP-2/3

JUL 27 2010

KCC WICHITA

STATE: KANSAS COUNTY: BARTON 30-20S-15W
FIELD: PAWNEE ROCK FLD (ARB) NW SW NW
OPER: IANNITTI OIL 3630 FSL 4950 FEL SEC
WELL: 3 UNRUH WELL CLASS: DO ELEV: 2055 KB
API: 15-009-24485 STATUS: OIL 2054 DF
SPUD: 08/05/91 COMP: 08/27/91 2050 GR
DTD: 3870 LTD: 3869 FTD: ARBUCKLE PBTD: 3862

LOC: 2 3/4 MI NW PAWNEE ROCK, KS

IP: COMP 8/27/91, IPP 60 BOPD, 1 BW, GTY 39 PROD ZONE- ARBUCKLE 3798-3811
NO CORES, FOUR DSTS

LOG TOPS:

ANHYDRITE	1054 1001	DOUGLAS	3413 -1358
BSE ANHYDRITE	1078 977	BROWN LIME	3473 -1418
TOPEKA	3126 -1071	LANSING	3546 -1491
HEEBNER	3383 -1328	BSE KANSAS CITY	3709 -1654
TORONTO	3400 -1345	ARBUCKLE	3773 -1718
TD	3870 -1815		

LOG TYPES: CNL, DI;

CSGS: 8 5/8 @ 1065 W/550 SX, 5 1/2 @ 3869 W/150 SX; TBG: 2 7/8 @ 3857; DRLG COMP
08/12/91 RIG REL 08/13/91

(OVER)

COPYRIGHT 1991 PETROLEUM INFORMATION CORPORATION

DATE 12/06/91 CARD #00031-KS