

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24513-00-00
Spot: NESWNW Sec/Twnshp/Rge: 30-20S-15W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: UNRUH Well #: 4
County: BARTON Total Vertical Depth: 4100 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1064	0	400 SX
PROD	5.5	4098	0	125 SX

Well Type: SWD UIC Docket No: D26646.0 Date/Time to Plug: 07/21/2010 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (865) 675-1554

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 300# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tried to pull casing - had bottom sanded off above perfs.
Could not pull any casing - decided not to pull casing - will plug with tubing.
Perfed at 1600' - 1150' - 700' - 150'.
Ran tubing to 1595' - pumped 40 sxs cement with 200# hulls.
Pulled to 1157' - pumped 50 sxs cement with 200# hulls.
Pulled to 686' - circulated with 60 sxs cement.
Pulled tubing - tied onto backside - circulated out casing with 10 sxs cement.
Shut in.

Perfs:

Top	Bot	Thru	Comments
4003	4013		
3995	3998		
3982	3986		
3974	3980		
3958	3960		
3953	3955		
3936	3939		

Remarks: ALLIED CEMENTING COMPANY-TICKET #36779.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED

JUL 29 2010

Form CP-2/3

JUL 27 2010

KCC WICHITA

STATE: KANSAS COUNTY: BARTON 30-20S-15W
FIELD: PAWNEE ROCK NE SW NW
OPER: IANNITTI OIL 3630 FSL 4290 FEL SEC
WELL: 4 UNRUH ELEV: 2040 ES
API: 15-009-24513
SPUD: 07/15/92
WELL CLASS: IW
STATUS: W-INJ
COMP: 08/28/92
DTD: 4100 LTD: FTD: ARBUCKLE PBD: 4084

LOC: 2 1/2 MI NW PAWNEE ROCK, KS

IP: COMP 8/28/92, WTR INJ WELL INJ ZONE - ARBUCKLE 3936-4013(GROSS)
NO CORES, ONE DST

LOG TOPS:

ANHYDRITE	1045 995	LANSING	3493 -1453
TOPEKA	3130 -1090	KANSAS CITY	3714 -1674
HEEBNER	3389 -1349	ARBUCKLE	3799 -1759
BROWN LIME	3478 -1438		
TD	4100 -2060		

CSGS: 8 5/8 @ 1064 CMT, 5 1/2 @ 4098 W/125 SX; RIG REL 07/20/92

DSTS: DST # 1 (ARBUCKLE) 3802-3909, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI 30 MIN,
REC: 10 FT MUD, IFP 55, FFP 55, IFP 55, FFP 55, ISIP 55, FSIP 754, IHP 1856, FHP
1856;

PERFS: PERF (ARBUCKLE), 3936-3939, 3953-3955, 3958-3960,

(OVER)

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION

DATE 05/14/93 CARD #00005-KS