

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21132-00-00
Spot: NWNENW Sec/Twnshp/Rge: 30-16S-16W
350 feet from N Section Line, 1374 feet from W Section Line
Lease Name: URBAN D Well #: 3
County: RUSH Total Vertical Depth: 3580 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1114		WITH 400 SX CMT
PROD	4.5	3579	0	WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2010 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 50 SX CMT WITH HULLS. PERFORATE 4 1/2" @ 1140'. PULL TBG TO 1200' & CIRCULATE CMT UP 4 1/2" & 8 5/8" X 4 1/2" ANNULUS. PULL TBG & TOP OFF HOLE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2010 12:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TUBING TO 3411' & PUMPED 50 SX CMT WITH 250# HULLS MIXED. PERFORATED 4 1/2" @ 1145'. PULLED TBG TO 1200'. PUMPED 350 SX CMT DOWN TBG. CIRCULATED CMT GOOD UP 4 1/2" & 8 5/8" X 4 1/2". PULLED TBG & TOPPED OFF WITH WELL WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3476	3484		
3468	3472		
3452	3454		
3434	3438		
3412	3421		
3309	3316		
3294	3298		
3272	3276		
3240	3244		

Remarks: SUED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

NOV - 9 2010

KCC DODGE CITY

RECEIVED

NOV 15 2010

KCC WICHITA