

F 113.04

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20181-00-00  
Spot: SESWE Sec/Twnshp/Rge: 27-31S-4E  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WORKMAN Well #: 4  
County: COWLEY Total Vertical Depth: 3478 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215		140 SXS CMT
PROD	5.5	3470		135 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2010 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM INC Phone: (316) 524-1225

Proposed Plugging Method: SAND 50' ABOVE PERFS W/5 SXS , 35 SXS @ 2550', 265'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 10/19/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED 50' ABOVE OPENHOLE @ 3420', DUMP BAILED 5 SXS CEMENT ON TOP. RIH W/TBG @ 2550', GRESSEL OILFIELD ESTABLISHED CIRCULATION & PUMPED 35 SXS CLASS A 3% CC AND DISPLACED IN CASING, PRESSURED CASING, HELD OK. SHOT SQUEEZE HOLES @ 265'-266' SWEDGED INTO 5-1/2" CASING, ESTABLISHED CIRCULATION & PUMPED 205 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. GRESSEL OILFIELD CEMENT TICKET #35150.

Perfs:

Top	Bot	Thru	Comments
3470	3478	OH	

Inv. dt: 12/15/10  
Inv. #: 2011060294

Remarks:  
Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

RECEIVED  
OCT 28 2010  
KCC WICHITA

✓