

# 67.31

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-23560-00-00  
Spot: S2NENENW Sec/Twnshp/Rge: 33-34S-11W  
600 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: KEESECKER Well #: 1  
County: BARBER Total Vertical Depth: 2071 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 8.625 | 913        |             |         |
| COND   | 10.75 | 225        |             |         |

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2010 12:00 PM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: GREG DAVIDSON Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: \_\_\_\_\_ KCC Agent: STEVE PFEIFER

Actual Plugging Report:

LOST CIRCULATION AT 570'. PBTD 1378'. PRIOR TO PLUGGING, HOLE WAS PLUGGED BACK FROM 2071-1378' WITH CMT. 1ST PLUG AT 930' WITH 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TOPPED OFF 10 3/4" X 8 5/8" ANNULUS WITH 100 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

*Dr. dt: 12/15/10*  
*Dr. #: 204060276*

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: DP

District: 01

Signed \_\_\_\_\_

*Stephen J. Pfeifer*

RECEIVED

AUG - 3 2010

KCC DODGE CITY

TECHNICIAN RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 09 2010

CONSERVATION DIVISION  
WICHITA, KS