

105.79

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19234-00-00
Spot: NENWNWSW Sec/Twnshp/Rge: 20-33S-3E
2322 feet from S Section Line, 4930 feet from E Section Line
Lease Name: WEST RAINBOW BEND UNIT Well #: 8
County: COWLEY Total Vertical Depth: 3255 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	3030	400	100 SX
PROD	5.188	3225	400	

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/11/2010 1:00 PM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: Company: KIVETT PLUGGING & PIPE Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/12/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3110', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL, 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 3050'. CUT CASINGS @ 400', LAYED DOWN 6.625" CASING AND 400' 5.1875 CASING. RIH W/20' OF 6.625" CASING. RIH W/TBG @ 360', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 575 SXS 60.40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-12-2010. CONSOLIDATED CEMENT TICKET #24113.

Perfs:

Top	Bot	Thru	Comments
3225	3255	OH	BARTELSVILLE

Inv. dt: 12/15/10
Inv. #: 2011060259

Remarks:
Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
AUG 12 2010
KCC WICHITA
Form CP-2/3

✓