

5/108.10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20736-00-01
Spot: SWNESE Sec/Twnshp/Rge: 1-18S-14W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: REIDEL OWWO (DEMEL) Well #: 1
County: BARTON Total Vertical Depth: 3326 feet

Operator License No.: 31174
Op Name: BIG HORN OIL CO., INC.
Address: PO BOX 263
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.626	792	0	
PROD	5.5	3325	1550	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: BIG HORN OIL CO., INC. Phone: (620) 786-5514

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/22/2010 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Pumped 50 sxs on bottom with 200# hulls - 3% c.c.
Waited four hours to cut casing - cut casing at 1550'.
Pulled to 1500' - pumped 125 sxs cement with 300# hulls.
Pulled to 750' - pumped 50 sxs cement.
Pulled to 450' - pumped 50 sxs cement.
Pulled to 200' - circulated to surface with 65 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3325	3326		
3256	3258		
3252	3254		
3169	3173		
3157	3160		
2950	2952		

12/07/10
2011060798

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

RECEIVED Form CP-2/3

NOV 01 2010

KCC WICHITA

OCT 26 2010