

#122.69

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01399-00-00
Spot: SESESW Sec/Twnshp/Rge: 16-9S-21W
330 feet from S Section Line, 2310 feet from W Section Line
Lease Name: ANDRESON Well #: A13
County: GRAHAM Total Vertical Depth: 3775 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	152	0	125 SX
PROD	5.5	3774	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2010 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 305 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 10/26/2010 3:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Perfed at 1690' - 900' - 200'.
Pulled tubing to 3700' - pumped 75 sxs 60/40 pozmix - 4% gel - followed with 14 sxs gel and 100# hulls.
Pulled tubing to 1750' - pumped 90 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 850' - pumped 80 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing - topped off 5 1/2" with 15 sxs 60/40 pozmix - 4% gel - 300# pressure.
Had casing hanger - orange peeled and 2" collar put on 5 1/2" x 8 5/8" annulus with 14 sxs cement with 300# pressure.
Plug complete.

Perfs:

Top	Bot	Thru	Comments
3732	3738		

12/07/10
20110652.99

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Bruce D. Basye
(TECHNICIAN) CM

RECEIVED Form CP-2/3

NOV 01 2010

OCT 28 2010

KCC WICHITA