

\$124.09

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23240-00-00
Spot: SENWNENW Sec/Twnshp/Rge: 32-6S-22W
350 feet from N Section Line, 1790 feet from W Section Line
Lease Name: LESH Well #: 1-32
County: GRAHAM Total Vertical Depth: 3818 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208	0	150 SX CMT.
T1	2.375	3810		
PROD	5.5	3815	0	440 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2010 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JIM BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2010 9:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 14 sxs gel spacer - followed with 185 sxs 60/40 pozmix - 4% gel with 300# hulls. S.I.P. 200#. Pumped 10 sxs 60/40 pozmix - 4% gel down 8 5/8" x 5 1/2" annulus to bring to surface.

Perfs:

Top	Bot	Thru	Comments
3674	3700		
12/07/10 2011060291			

Remarks: SWIFT SERVICES, INC.-TICKET #18118.

Plugged through: CSG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

RECEIVED

OCT 08 2010

KCC WICHITA

Form CP-2/3

OCT 04 2010