

#113.B

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23648-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 26-7S-20W
1470 feet from S Section Line, 1280 feet from E Section Line
Lease Name: RABOURN Well #: 1-26
County: ROOKS Total Vertical Depth: 3481 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208	0	150 SX CMT.
T1	2.375	3457		
PROD	5.5	3480	0	440 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2010 12:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JIM BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2010 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 15 sxs gel spacer - followed with 190 sxs 60/40 pozmix - 4% gel and 200# hulls. S.I.P. 800#.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 15 sxs to bring to surface.

Perfs:

Top	Bot	Thru	Comments
3448	3458		
3442	3445		

12/07/10
2011060291

Remarks: SWIFT SERVICES, INC.-TICKET #18121.

Plugged through: CSG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

RECEIVED

OCT 08 2010

KCC WICHITA

Form CP-2/3

OCT 04 2010